

Sandy Hill Heritage Study

Descriptive sheet

323 Daly Ave

Municipal Address	323 Daly Avenue	Building name		323 Daly Ave
Legal description		Lot:	Block:	Plan:
Age/Date of Construction	Between 1904-1907	Original use		
	Detween 1904-1907	Present use		



Source: Ron J. Roy Date: 2007/22/04

Heritage Status

Existing heritage building	Name:		
	Bylaw / date:		
Eviating havitage district	Name:	Besserer St/Daly Ave/Augusta St/Cobourg St	
Existing heritage district	Bylaw / date:	308-82	
Potential Heritage Building:	not defined		
Potential Heritage District:	not defined		
Comments:			

Phase 2 Evaluation Results

Prepared by: Date:

Score	100 - 70	69 - 55	55 - 40	39 - 0
Group	1			

History

Prepared by: Chris Wiebe, Carolyn Van Sligtenhorst Date: 2007/05/08

Age/Date of Construction (Factual/Estimated)

Between 1904-07.

COHF: Pre-1912 M1878: Nothing on site. M1888(1901): Same

M1902(1912): 2 1/2 storey building with shingled roof, front porch.

M1902(1922): Same - building is brick. M1948: Same - roof is tar & gravel.

M1956: Same

Events

Persons/Institutions

D1903 - Not listed

D1908: Stuart E De la Ronde D1912: Irving B. Miles D1915: Joseph P Fisher D1922: Joseph P. Fisher D1934 - Jas. J O'Leary (Alma) D1940: Jas. J O'Leary (Alma) D1948: James J O'Leary (Alma)

Developmental Context

This house is part of early twentieth century efforts for the development of Daly Avenue for residential use, within the Besserer estate.

Summary/Comments on historical significance

The historic significance of this property lies it in its age (constructed in 1904-07), its associations with important individuals (such as Stuart E De La Ronde) and its role in the continuing development of the residential character of Daly Avenue and the development of the Besserer Estate.

Historical sources

- •City of Ottawa heritage file PD04-OHD4300/DALY00323
- •June 1878 Insurance Plan of Ottawa, Ontario. National Map Collection, Public Archives Canada.
- •January 1888 Key Plan of Ottawa and Vicinity. (Revised 1901). National Map Collection, Public Archives Canada.
- •September 1902 Key Plan of the City of Ottawa, Ontario. Volume 1 (Revised 1912). National Map Collection, Public Archives Canada.
- •September 1902 Insurance Plan of the City of Ottawa, Ontario. Volume 1 (Revised 1922). National Map Collection, Public Archives Canada.
- •November 1948 Fire Insurance Map, Ottawa, Ontario. Volume 2. National Map Collection, Public Archives Canada.
- October 1956 Fire Insurance Map, Ottawa, Ontario. Volume 2. National Map Collection, Public Archives Canada.
- The Ottawa City Directory, 1903, 1908, 1912, 1915, 1922, 1940, 1948.

323 Daly Ave

Architecture Prepared by: Chris Wiebe Date: 2007/02/08

Architectural characteristics and design

Property characteristics: Single use residential. Detached, 2 1/2 storey with rectangular plan, off-center entry and occupied basement. 2 storey addition with wood at rear. Site features consist of a garden.

Exterior elements: Sloped roof of asphalt shingles with gable end; 1 brick chimney. Decorative roof elements include returned eaves and decorative wood fascia and wood brackets in eaves. Exterior brick wall with string courses, stone lintels, stone sills and voussoirs. Angled wood bay window at ground floor. Coursed rock-faced stone foundation.

Windows and doors: Rectangular wood double hung 2x4 windows and wood oriole windows at upper floors with decorative glass. Wood storm windows. Single metal front door with window in door and wooden screen door.

Other features: 1 storey wood porch with brick base, wood columns, wood balustrade, sloped roof, pediment and treillage and round arched decorative window in pediment.

Comments:

Exceptional details.

Architectural Stylistic Influences

Queen Anne Revival

Designer/Builder/Architect

N/A

Architectural integrity

High: Non-original door and rear addition slightly affect the integrity.

Other

Summary/Comments on architectural significance

This is a good example of a fairly intact Queen Anne Revival residence, with characteristic sloped roof with projecting eaves and decorative supporting brackets, and irregular massing displayed in the angled bay window, oriel windows and generous porch extending across the front facade. The Edwardian stylistic influence that began to appear post-1900 is manifested in the strong stone lintels, Classical detailing at the oriel window surrounds and front porch, and the decorative mullions in the upper window sashes. These significant elements should be maintained in future renovations.

Context Prepared by: Date:

Existing heritage building	Name:	
	Bylaw / date:	
Existing heritage district	Name:	Besserer St/Daly Ave/Augusta St/Cobourg St
	Bylaw / date:	308-82



Source: Ron J. Roy Date: 2007/22/04

Compatibility with surroundings:

Pattern of site use: Typical front and side set backs

Use: Typical (residential)

Height/Volume: Typical

Materials: Typical (brick, shingle)

Typology: Type 1(p,b)

Community context/Landmark status

This property makes a strong contribution to the history and architecture of the neighbourhood.

Summary/Comments on environmental significance

This property reinforces the pattern of the block in which it sits.

		Pre 1890	1891 - 1900	1901 - 1910	1911 - 1925	1926 - 1950	1951 +	Score
	Age/Date of Construction	10	8 - 9	⊘ 6-7	4 - 5	1 - 3	0	7/10
≿				High	Medium	Low	N/A	
HISTORY	Events / Persons			4 - 5	3	√ 1 - 2	0	1/5
王				High	Medium	Low		
	Developmental Context			11 - 15	<u></u> 6 - 10	1 - 5		9/15
	Total							17/30

		Proportion/Scale	Detail/Craftsmanship	Coherence	Score
	Architectural characteristics	4/5	5/5	5/5	14/15
		Strong	Medium	Weak	
TURE	Stylistic Influence	<u></u> 11 - 15	6 - 10	0 - 5	13/15
EC		Renowned	Known	Unknown	
RCHI	Designer / Builder / Architect	3 - 5	1 - 2	<u></u> 0	0/5
₹		High	Medium	Low	
	Architectural Integrity	⊘ 4 - 5	2 - 3	0 - 1	4/5
	Total				31/40

		Sets example	Reinforces pattern	Compatible with pattern	Incompatible with pattern	Score
EXT	Compatibility with surroundings	<u></u> 15 - 20	10 - 14	5 - 9	0 - 4	18/20
CONTE		Strong	Moderate	Weak	No	
ဗ	Community Context/Landmark Status	⊘ 7 - 10	4 - 6	1 - 3	0	7/10
	Total					25/30

Phase II score	73/100

			_
Heritage Status	Group	1	